BRUHAT BANGALORE MAHANAGARA PALIKE

Item No.38

APPROVED SCHEDULE - B

Tender Notification No: BBMP/ EE /Btp/Ten/05/2012-13 Dated: 30-07-2012

Name of Work: Providing Chainlink fencing to Storm Water Drain at selected reaches in ward No.10

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of NN sreenivasaiah	
				In Figures	In Words
1	255.00	Supplying and fixing M.S Rectangular poles made out of 2 equal angles of 65X65X6mm welded together and fixed in CC(1:2:4) with 2 Nos 16mm dia M.S hold fast rods each of length 25cms. Including cost of all materials cutting, bending scaffolding wherever necessary , nidcedly finishing the welded joints with all lesad lifts and as per the directions of the Engineer in-charge of the work and including providing 2 coats of approved quality paint over one coat of shop painting (excluding cost of earthwork and concrete) P 232, Ino 37.2, PWDSR 2010-11	M	**710.64**	Rupees Seven Hundred Ten and Sixty Four Paise Only
2	432.50	Providing **Chain Link Fencing** 50 mm size of 8 guage property striched between rectangular poles and fixed with suitable bolts and nuts, the free ends shall be welded to the pole and block pipe at top and bottom as required, including cost of all materials, labour, lead and lifts, cutting, bending scafolding wherever necessary, wastage and lapping etc., complete as per the directions of the Engineer-in-charge of the work and including providing 2 coats of approved quality paint over one coat of shop painting **(P.231/I 37.3 PWD SR - 2010-11).**	Sqm	**535.01**	Rupees Five Hundred Thirty Five and One Paise Only
3	519.00	Providing and fixing **M. S. Block Pipe** of 38 mm dia, of heavy guage of 1:4, including removing the bends, cutting the pipe in between the two verticle poles (M. S. Rectangular Poles) and spot welding the chain link with M. S. Block Pipe, including cost of all materials, wastage in cutting and scaffolding wherever necessary, with all lead and lift as directed by the Engineer-in-charge of the work etc., complete including 2 coats of approved quality paint over one coat of shop painting **(P.231/I 37.4 PWD SR - 2010-11).**	M	**246.69**	Rupees Two Hundred Forty Six and Sixty Nine Paise Only
4	10.63	Dismantling size stone masonry I n clay mortar/lime mortar and staking the sizae stone within a radius of 50m and removing the debris to a distance upto 200m P.235, I.37.48 PWDSR 2010-11		**110.92**	Rupees One Hundred Ten and Ninety Two Paise Only
5	234.24	Removing B.S. slab of Drain and stacking. (P No.24 / i 5.32 SR 2010-11)	Sqm	**40.20**	Rupees Forty and Twenty Paise Only

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of NN sreenivasaiah	
				In Figures	In Words
6	197.64	KSRRB 300-1 : Earthwork excavation by manual means in ordinary soil involving an average horizontal throw upto 2m meters and an average lift upto 0.5m, excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications complete as per specifications. (P No.126 / i 19.1 SR 2010-11)	Cum	**52.79**	Rupees Fifty Two and Seventy Nine Paise Only
7	43.92	KSRRB M300-53: Construction of embankment with approval material Gravel/Murrum with all lifts and leads,transporting to site, spreading, grading to required slope and compacting to meet requirement Table 300-2 complete as per specifications. (which includes cost of gravel / murrum, watering charges & compaction by vibratory roller) (P No. 133 / i 19.60 SR 2010-11)	Cum	**138.07**	Rupees One Hundred Thirty Eight and Six Paise Only
8	43.92	KSRB 4-1.3: Providing and laying in position plain cement concrete mix 1:4:8 using 40mm and down size graded granite metal machine, concrete laid in layers not exceeding 15 cms. Thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specification No.KBS 4.1, 4.2 (P No. 12 / i 4.3 SR 2010-11)	Cum	**3148.14**	Rupees Three Thousand One Hundred Forty Eight and Thirteen Paise Only
9	585.60	KSRB 4-6.4: Providing and removing centering, shuttering, strutting, propping etc.., and removal of form work for vertical surface such as walls at any thickness, including attached pilasters, buttresses,plinth and string courses cost of all materials,labour complete as per specifications. (P No. 14 / i 4.31 SR 2010-11)	Sqm	**187.81**	Rupees One Hundred Eighty Seven and Eighty One Paise Only
10	120.78	KSRB 4.2.2 : Providing and laying in position reinforced cement concrete of mix 1:1.5:3 with 20mm and down size graded granite metal machine mixed, concrete laid in layers not exceeding 15 cms thick, vibrated for all works in foundation plinth and ground floor level for roof slab, staircase, lintels, retaining walls, walls (any thickness) including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks plain window cills,fillets etc.., including cost of all materials, labour, HOM of machinery, curing, complete as per specifications. Specification No. KBS 4.1, 4.6 (P No. 12 / i 4.11 SR 2010-11)	Cum	**4607.99**	Rupees Four Thousand Six Hundred Seven and Ninety Nine Paise Only

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of NN sreenivasaiah	
				In Figures	In Words
11	96.62	KSRB 4.9.2 : Providing T.M.T steel reinforcement for RCC work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and westage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications. (P No. 16 Item No.4.46 PWD SR 2010-11)	Qntl	**4877.00**	Rupees Four Thousand Eight Hundred Seventy Seven Only
12	234.24	Refixing stone slabs of drains and pointing in C.M. (1:3) (P No.24 / i 5.33 SR 2010-11)	Sqm	**48.22**	Rupees Forty Eight and Twenty Two Paise Only
13	197.64	Leadfor disposalof debris shall be payable at the following rates	Cum	**0.00**	

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92